



SWIN
BUR
* NE *

SWINBURNE
UNIVERSITY OF
TECHNOLOGY


The Journey for 5 Stars

Vince Persi, Swinburne University Major Projects

Mark O'Dwyer H2o Architects

CRICOS provider 00111D

The Site




Features of the original buildings:

- asbestos throughout
- air quality was stale due to old mechanical plant
- insufficient space and impractical design layouts
- low light levels
- outdated




The Journey for 5 Stars



With the constant expansion of the University and a need for contemporary student research labs, classrooms and academic staff offices, a more suitable building was required.





Advanced Technologies Centre (ATC)



- The ATC is the first educational building in Australia to be awarded 5 Star Greenstar accreditation on Educational V1 tool



Advanced Technologies Centre (ATC)



Advanced Technologies Centre (ATC)



Features include improved:

- Indoor air quality and ventilation
- Thermal comfort
- Lighting levels
- Acoustics



Malaysia




Why Go Green ?



- The Green Building Council reports that studies indicate that occupants of healthy buildings show increased productivity
- Surveys have also shown that a healthy building will promote happier and healthier people in your organisation
- As a University we have duty of care to promote green awareness. The best way to do this is to lead by example.



Why Go Green ?




- Swinburne wanted to make a real contribution to lower the carbon footprint on our campus
- The University wanted to provide a working example of sustainability for our students.



Advanced Technologies Centre (ATC)

- An example of sustainability has been the incorporation of bricks from the original building into internal walls of the ATC






SWIN
BUR
NE

SWINBURNE
UNIVERSITY OF
TECHNOLOGY


H2o

SWINBURNE
UNIVERSITY OF
TECHNOLOGY
ADVANCED
TECHNOLOGIES
CENTRE











SWINBURNE
UNIVERSITY OF
TECHNOLOGY
ADVANCED
TECHNOLOGIES
CENTRE



Planning flexibility from peripheral balcony access



Sun filled campus external congregation space



Flexible retractable seat glazed auditorium




Clearspan lower levels bridged by large beams







Promotion with glazed shopfront to main frontage



Strongcell destruction testing space



Iconic precast concrete facade





















SWINBURNE
UNIVERSITY OF
TECHNOLOGY
ADVANCED
TECHNOLOGIES
CENTRE



Maximise internal thermal mass & orientation



Maximise internal thermal mass









Passive Venting & Daylighting to vertical shafts

Optimise Vertical Circulation Shafts
Skylighting & Passive Venting
Improve internal conditions
Localise interfloor access
Connection to light courts



Passive Venting and Daylighting



Passive Venting and Daylighting

Natural ventilation activation disengages A/C





Natural Venting / openable windows




Sustainable Mechanical: Chilled Beams





Daylight into lower level light courts





Energy efficient lifts & escalators



Energy efficient lifts & escalators



Concrete slabs over upper level accommodation

FROM SPRING TO LINDENHART
MADE FROM TO EXTEND, ALICE WOOD PAPER




Sustainable Materials / self finished




Sustainable Materials: Reuse existing onsite bricks




Sustainable Materials: Recycled timber flooring




Sustainable Materials: Recycled timber flooring



Sustainable Materials: Recycled timber flooring




Sustainable Materials: Local recyclable carpet tiles




Reconfigurable accommodation




Reconfigurable accommodation



Low water landscaping



Gravity fed holding tanks / efficient urinals



SWINBURNE
UNIVERSITY OF
TECHNOLOGY
ADVANCED
TECHNOLOGIES
CENTRE

Built environment forces

Green Star rating system

Swinburne University of Technology
Advanced Technology Centre / SUT ATC



Waterman (AHW) International as the
designated Green Star professional

CAT	PTS	AUD
MAN1	2.0	\$100K

Green Star Professional

Comprehensive pre-commissioning quality monitoring are required to be carried out by the Contractor. Mechanical services are to be commissioned to ASHRAE Commissioning Guideline 1-1996.

All knowledge on commissioning to be transferred to the building owner manager

Greenstar Sustainability Targets

The Swinburne ATC building complex design, construction, commissioning and tuning are to be registered and possibly accredited under the Green Star Education rating tool as developed by the Green Building Council Australia (GBCA).

Specific credit points under the GBCA education tool have been targeted to allow the building to achieve a 5 star Green Star design rating.

The Contractor and associated sub-contractors, including the mechanical contractor, will have responsibilities, under the requirements of the Green Star rating credits, that will need to be carried out to ensure possible future accreditation under the scheme is achievable.

The following is a summary of the Green Star credits being targeted:

Green Star Identifier	Green Star Category	Comments
Man-1	Green Star Professional	<ul style="list-style-type: none"> Wateman International are the designated Green Star professional
Man-2	Commissioning Clauses	<ul style="list-style-type: none"> Comprehensive pre-commissioning quality monitoring are required to be carried out. Mechanical services are to be commissioned to ASHRAE Commissioning Guideline 1-1996. All knowledge on commissioning to be transferred to the building owner manager
Man-3	Commissioning - Building Tuning	<ul style="list-style-type: none"> A twelve month building tuning process is to be implemented during the defects liability period involving monthly monitoring and reporting, with a full recommission and report at the end of twelve months
Man-4	Independent Commissioning Agent	<ul style="list-style-type: none"> An Independent Commission Agent, Cornish Pty Ltd, has been appointed during the design period and will monitor and verify the commissioning of all building systems. The contractor is to work with the Independent Commissioning Agent and Engineer to achieve the commissioning targets for the project
Man-5	Building Guides	<ul style="list-style-type: none"> Contractor shall provide input into Building Users Guide and a Building Maintenance Guide in line with GBCA requirements
Man-6	Environmental Management	<ul style="list-style-type: none"> Contractor shall implement a comprehensive, project specific, Environmental Management Plan (EMP) for the works in accordance with section 4 of the NSW Environmental Management System Guidelines - 1998. Services sub-contracted shall participate in this EMP Contractor to have valid ISO 14001 Environmental Management System accreditation
Man-7	Waste management	<ul style="list-style-type: none"> Contractor to have a Waste Management Plan. Percentage by weight to be re-used or recycled to be 80%. Services sub-contractors participate in the scheme
Man-10	Learning Resources	<ul style="list-style-type: none"> Three of the building complex's environmental attributes to be displayed and measurable

CAT PTS AUD
MAN2 2.0 \$60K

Remove rubbish and surplus material from the site and clean the work throughout, to SUT FSG approved standard. Direct any queries about this requirement to the SUT FSG Project Coordinator BEFORE commencing work on site. Before arranging handover inspections and prior to completion, finish, clean, and make good the Works including:

- Clear and remove surplus materials, dirt, debris and the like.
- Repair damage and defects to adjacent properties resulting from the Works.
- Repair damage, stains and blemishes, or replace work where required.
- Clean all finished surfaces
- Issue as-built details
- Commission, test and ensure services and equipment are connected and operating properly.

2.7.5 Commissioning and Pressure Testing

Refer to Section 2.1.11 Sustainability, the Services Engineer Specifications and the SUT FSG Manuals for additional Commissioning details.

Airtightness fan testing

The external building fabric shall be tested for airtightness on completion of the building shell, by an approved independent testing authority appointed by the Contractor. The Light Courts are considered as external spaces

The Contractor shall be responsible for carrying out the airtightness tests and preparation of reports in accordance with the requirements of the Air Tightness Testing and Measurement Association (ATTMA) publication 'Measuring Air Permeability of Building Envelopes'.

Variable flow portable fans shall be temporarily placed in an external doorway or similar external opening. The test fans shall be switched on and the air flow adjusted to achieve an internal pressure of 50-60 Pa for Laboratory spaces and 20 Pa for other spaces. The total air flow through the fan and the pressure differential between inside and outside shall be recorded in accordance with the ATTMA requirements.

A maximum air permeability rate of 5.0m³/hour.m² shall be achieved. If this rate is not achieved, the Contractor shall undertake remedial work as necessary to further seal the building envelope.

Further pressure testing shall be undertaken until the required maximum air leakage rate is achieved.

The Contractor is responsible for the making good or sealing of leaks to the building envelope as necessary to achieve the required air leakage rate.

Tests shall be carried out prior to the date for practical completion.


2.7.6 Practical Completion and Inspection

A Notice of Practical Completion shall not be issued until in the opinion of the Superintendent, all the items noted during final inspections have been completed sufficiently to render the building fit for occupation and use by the University. (Refer to Special Conditions of Contract).

The Notice of Practical Completion shall be referred to the Superintendent before issue to ensure that:

- Insurances are arranged by the University before handover
- Copies of the Contractors Insurance policies
- An Occupancy Certificate or Certificate of Final Inspection has been issued by the Building Surveyor inclusive of the essential services determination.
- Security and fire protection services have been commissioned and are operational.
- Written approvals have been issued by all Local and State Authorities concerned with the project.
- A list of final items of rectification has been issued.


Commissioning Clauses



CAT	PTS	AUD
MAN3	1.0	\$100K

Building Tuning

An Independent Commission Agent, Commtech Pty Ltd, has been appointed during the design period and will monitor and verify the commissioning of all building systems in the later stages of construction. The contractor is to work with the Independent Commissioning Agent and Engineer to achieve the commissioning targets for the project



CAT	PTS	AUD
MAN4	1.0	\$50K

Independent Commissioning

PHASE	Requires Architect Participation	Requires Engineer Participation	Requires SUT Occupant Participation	Requires SUT Maintenance Participation	Requires SUT Facilities Participation	Requires Construction Contractor Participation	Requires Construction Sustainability Coordinator	Requires Sub Contractor Participation
Phase 1: Exploring Sustainable Approaches								
Phase 2: Educating Future Occupants on Sustainable Approaches during Briefing sessions								
Phase 3: Documenting Sustainable Approaches								
Phase 4: Re-acquainting Future Occupants on Sustainable Approaches prior to Tender								
Phase 5: Requesting Sustainability Credentials from potential Construction Contractors to inform Tender list								
Phase 6: Briefing Construction Contractors on Sustainable Approaches during Tender								
Phase 7: Compilation of Sustainability details by Construction Contractors for Tender bid								
Phase 8: Reviewing of Sustainability details submitted by Construction Contractors in Tenders								


CAT PTS AUD
MAN5 2.0 \$10K

Building Reporting

PHASE	Requires Architect Participation	Requires Engineer Participation	Requires SUT Occupant Participation	Requires SUT Maintenance Participation	Requires SUT Facilities Participation	Requires Construction Contractor Participation	Requires Construction Sustainability Coordinator	Requires Sub Contractor Participation
Phase 9: Informing Construction Contractor /Coordinator / Sub Contractors of Sustainable Approaches at the Commencement of Construction								
Phase 10: Informing Construction Contractor /Coordinator / Sub Contractors of Sustainable Approaches when Trade Forman Commence								
Phase 9: Assisting Construction Contractor /Coordinator / Sub Contractors During Construction								
Phase 10: Commissioning Sustainable Approaches during Construction								
Phase 11: Handing-over Sustainable Approaches to SUT at Completion of Construction								
Phase 12: Reacquainting Building Occupants with Sustainable Approaches at the commencement of Occupancy								
Phase 13: Confirming Building operates in accord with Sustainable approaches								
Phase 14: Reviewing Sustainable Operation with Building Occupants regularly for up to a year after Occupancy								


CAT PTS AUD
MAN5 2.0 \$10K

Building Reporting




CAT	PTS	AUD
MAN10	1.0	\$50K

Learning resources




CAT	PTS	AUD
TRA1	2.0	\$2K

Reduced carparking



CAT	PTS	AUD
TRA2	1.0	\$10K

Fuel efficient transport



CAT	PTS	AUD
TRA3	2.0	\$30K

Cyclist facilities



CAT	PTS	AUD
TRA3	2.0	\$30K

Cyclist facilities



SWINBURNE
UNIVERSITY


GLENFERRIE RAILWAY
STATION

SWINBURNE
UNIVERSITY

SUT ATC

CAT	PTS	AUD
TRA3	2.0	\$30K

Cyclist facilities



SWINBURNE
UNIVERSITY

GLENFERRIE RAILWAY STATION

150 ADDITIONAL
BIKE PARKS IN BLD
EW

SWINBURNE
UNIVERSITY

SUT ATC

CAT	PTS	AUD
TRA3	4.0	\$100K

Additional Cyclist facilities



GLENFERRIE
RAILWAY
STATION

SWINBURNE
UNIVERSITY


SWINBURNE
UNIVERSITY

SUT ATC

BUS STOP

CAT	PTS	AUD
TRA4	5.0	\$NIL

Proximity to Public Transport







CAT	PTS	AUD
Wat1	4.0	\$200K

Underground water tanks



CAT	PTS	AUD
Wat1	4.0	\$200K


Roof top water tanks



CAT	PTS	AUD
ENE1	2.0	\$900

Lower Greenhouse gas / PVs


Energy model penalises escalators in lieu of lifts and stairs



CAT	PTS	AUD
ENE1	NIL	????

Penalised for escalators

Reused existing facades insufficient to achieve points as >50%



CAT	PTS	AUD
MAT2	NIL	N/A

Recycle existing facades

Reused existing bricks from demolished buildings on site and recycled red gum stumps for Ground Level flooring, does not achieve points as construction cost insufficient in overall total (20%)



CAT	PTS	AUD
MAT3	NIL	\$300K

Recycle bricks & timber



CAT	PTS	AUD
MAT3	NIL	\$300K

Recycle bricks & timber



Workstation Screen Fabric
Finish: Knoll Textiles Mica 121



WS2 Workstation



CH4: Stylecraft
Café, Conference
Chair



CH2: Stem Task
Chair
Finish: Charcoal



CH1: Stem High
Task Chair



Dr-C: Table Wood Top
Sliding Storage Unit
Finish: White

CAT	PTS	AUD
MAT13	3	\$350K


Specify sustainable furniture



CAT	PTS	AUD
IEQ11	NIL	\$50K

Glare control / internal blinds

CFD Energy modelling requires at least \$60,000 AUD cost for no ongoing benefit, aside from achieving 3 Green Star points



CAT	PTS	AUD
IEQ2	NIL	(\$60K)

Air Exchange/CFD modelling

FINISHES LEGEND / SCHEDULE

REVISION	DATE	DETAILS
1	01.07.2008	Draft Issued for Review and comment and Cost Plan
2	14.07.2008	Draft Issued for Review and comment and Cost Plan
3	01.09.2008	Issued Approval / Prelender Estimate Issue / BOQ
4	11.09.2008	Tender Issue (Revised)
5	23.10.2008	Tender Issue
6	Not issued	Post Tender Issue (Revised to include tender addenda details)
A	10.02.2009	Issued for Construction / Adjustments in RED TEXT

1.0 PROJECT

Swinburne University of Technology Advanced Technology Centre (SUT ATC) on Sunwood Road at the Hawthorn Campus.

These details have been prepared by H2o architects. The representative of H2o architects is Mark O'Dwyer, 29 Northumberland Street, Colingwood, Victoria 3066, contactable on 03 9417 0900 / 0417 133 641.

2.0 GENERAL

2.1 This Project is sustainably design, and to be sustainably constructed and operated and will be registered with AGBR for a five star AGBR rating. Materials used on the project have been selected for environmental credentials. The key principles are:

- Low off-gassing materials (VOCs & Formaldehyde) - paints, carpets, mdf, etc
- Replace off gassing adhesives with sustainable / low VOC alternatives
- Reduce use of PVC
- Preference for materials and items with EMS details covering waste minimisation / energy consumption / emissions / materials
- Recycled or Forest Stewardship Council (FSC) certified timbers
- Zero Ozone Depletion Potential insulation


2.2 All product names listed in the schedules and specifications should be understood as requiring the supply and installation of the product by the Contractor.

2.3 The products must be as indicated - or similar as submitted for comment and approval by the Superintendent.

2.4 Painted finishes shall be in accordance with that outlined in the "Dulux-Duspec". The Paint types listed are a guide to performance and type, and the Contractor is required to source paints that are certified as sustainable products with low VOC / low emission / low off gassing qualities resulting with a proven low impact on the Indoor Air Quality (IAQ) when the space is occupied. Paint systems of these types are available from all main paint manufacturers and the Contractor is required to confirm these details and the sustainability certification, with the tender lodgment.


CAT PTS AUD
IEQ8&9 5.0 \$100K

No VOC & Formaldehyde



CAT	PTS	AUD
ECO1	NIL	????

Topsoil



CAT	PTS	AUD
ECO3	NIL	????

Reclaim Contaminated Land



CAT	PTS	AUD
ECO4	NIL	????

Ecological Value of Site



Thank you



Questions...

